



Acceptance tests for barrel modules

A few milestones:

- **First modules are due to arrive in March 03**
- **Module insertion schedule in spaceframe:**
 - **First sector (6 modules) in Oct 03 – Last in Oct 04**
- **It takes about 1 week per module to pass through all acceptance test stations**
- **One month for HV conditioning per sector**
 - **We have 16 sectors – do 2 sectors at a time**
- **We have 96 + 6 modules: 2 years of work for 1 technician – 1 year for 2 full-time technicians**

Conclusion: production level must start in July



Module flow in building 154

- **Receive module; enter in database**
- **Check dimensions – rework if necessary**
- **Check wire tension with 16-channel tester**
 - **compare with tension data from assembly site**
 - **mark wires that need replacement**
- **Check HV: continuity, broken wires etc**
 - **mark wires that need replacement**
- **Re-string bad wires if needed – re-seal wires**
- **Check for leaks**
- **Gain mapping**
- **HV conditioning for one month – rework if necessary**
- **Store module in shipping container in building 154**
- **Send to assembly building sector by sector**



Final HV conditioning and checks

- **Will be done at the surface building after all sectors will have been inserted**
- **No rework on individual wires done at this point**
- **There will be no access to services once the detector is lowered into the pit so last checks must be done at the surface**



Human resources at CERN

- **Technical staff: data taking, repairs, setup**
 - One highly qualified person in March
 - Second to start in September
 - Requested 2 CERN Summer students
- **Physicists: data analysis, coordination**
 - Myself full-time at CERN
 - Fred Kaioumov back at CERN in September
 - 2 physicists from Hampton and Duke in Fall
- **Others: consultancy**
 - Craig Kline: expert with module repairs
 - John Callahan: database
(here in Sept to work mostly on integration)



General status of the lab

- **All computers/networking installed**
- **General: tools, furniture purchased**
- **All gas lines installed**
- **Most hardware in place and working**
- **Storage rack built**
- **Database in place but needs to be customized**


Overall status of test stations

| | hardware | software | database |
|------------------------|------------------|-----------------|-------------------|
| dimensions | 80% | - | 0% |
| leak | 100% | 50% | 50% |
| 16-ch tension | 90% | 80% | 100% |
| stringing | 80% | 100% | not tested |
| HV checks | 100% | 20% | not done |
| HV conditioning | in design | 20% | not done |
| gain mapping | designed | 100% | not done |

Cabinet for HV conditioning

- Process 2 sectors at a time
- 2 modules per shelf, 6 shelves
- Circulate ventilation through 3 modules: type 1,2 3
- Active gas in series through 2 modules of the same type
- Condition the HV for a month
- Monitor current draw per module
- Operate in parallel with HV checks test station

- SS tubing
- flexible tubing
- flowmeters





Gain Mapper Status (Hampton built)

- Design exists: smaller version of Module Test Station
- Software written
- Some parts already purchased
- Construction should start in a few weeks

Current look in building 154

16-channel tension tester




Dimension and leak test



stringing station



HV test station



Long-term storage rack



Have rack, need modules